

Report of Bond Test

TESTED FOR: PSI
Special Test/Electrical Department

PROJECT: Sealmark

DATE: January 9, 1997

OUR REPORT NO.: 823-66078 SPT-60338

PSI Physical Testing Department received three (3) conditioned samples for bond testing.


Following are the results.

Bond Test

The samples were adhered to flat plates and pulled until material bond failed. The test was performed in our 60,000 pound Baldwin universal test machine.

Sample Id	Psi	Sample Id	Psi
7-1	49.0	Control-1	22.5
7-2	39.5	Control-2	25.0
7-3	38.0	Control-3	30.0
7-4	56.3	Control-4	25.0
7-5	<u>46.3</u>	Control-5	<u>27.5</u>
	Avg.: 45.8		Avg.: 26.0
CA-5	36.3		
CA-7	31.3		
CA-8	33.0		
CA-9	42.5		
CA-10	<u>37.5</u>		
	Avg.: 36.1		

Respectfully submitted,



Jason McCullough
Project Manager
Physical Testing Department

cc: 2-PSI(823)
ctn